

## AMENDMENT

### ROXBOROUGH ADMINISTRATIVE COMPLEX SUB-OFFICE

**Project Brief:** The contractor shall supply all required expertise, labor, tools, equipment, material and services to complete this scope of work according to specification and standard set by the Division. All unwanted materials should be discarded from project site to an approved dumping site.

#### Instructions To Tenderers

**Item 3.** See New layout drawing, item to be quoted in original scope of works.

**Item 4.** Change in square footage; item to be quoted in amendment and not the original scope of works.

**Item 5.** One additional door included. Item to be quoted in the amendment and not in the original scope of works

**Item 6.** Change in the size of the PVC window drapes; Item to be quoted in the amendment and not in the original scope of works.

**Item 7.** Desk sizes included; Item to be quoted in the amendment and not in the original scope of works.

**Item 9.** Change of seating material from foam to leather; Item to be quoted in the amendment and not in the original scope of works.

**Item 10.** Change to leather single chair seating instead of leather sofas. Item to be quoted in the amendment and not in the original scope of works.

**Item 14.** Change in the size of the refrigerator; Item to be quoted in the amendment and not in the original scope of works.

**Item 17.** This item has been omitted and should not be quoted for.

**Duration: 18 Days**

DESCRIPTION	UNIT	QTY	RATE	AMOUNT
<b>CUBICLE AREA</b>				
<p>3. Construct of 5 Feet x 5 Feet cubicle space by 53 inches in height. Wood panels used should be mahogany 1/4" to 1/2" thick. (e.g. Attached)</p> <p>The cubicle space should be made of gypsum material, mahogany side panels and infilled with glass (height of infilled glass is 24 inches) as seen in <b>Figure 3</b>. All preparatory work and materials shall be included in the cost.</p> <p><b>See New layout drawing</b></p>	Nr	02		<p><b>Item to be quoted in the original scope of works. New layout drawing included</b></p>
<b>EXECUTIVE OFFICE</b>				
<p>4. Construction of 12mm Clear Frosted Toughened/tempered Glass Partition Window Wall office space 7'- 8" x 17' by a height of 13' and Kitchen space 12'- 5" x 5'-8". Frosted height should be 6 feet high from floor level and 8 feet high for kitchen wall area.</p> <p><b>See New layout drawing</b></p>	Sf	202		
<p>5. Installation should cater for <b>(3) 32inches x 80inches</b> glass door with chrome handle;</p> <ul style="list-style-type: none"> <li>• 1 sliding glass doors at kitchen</li> <li>• 2 swing glass doors at office area and kitchen entrance</li> </ul> <p>All doors are to be fully frosted and made of toughened glass</p>	Nr.	03		
<b>WINDOW FINISHES &amp; FURNITURE</b>				
<p>6. Provision and placing of plastic interior PVC window drapes with appropriate tracks to fit space (5 feet x 6 feet; 14 feet x 6 feet; AND 12 feet 4 inches x 4 feet)</p>	Nr	03		
<p>7. Procure and install three (3) executive type desks to be placed in office area and cubicle spaces.</p> <p><b>1 L-Shape Executive Desk: (60 inches x 72inches)</b></p> <p><b>2 Executive Desk: (48inches x 32 inches)</b></p>	Nr	03		

9. Procure and Install <b>Two (2)</b> leather seating and leather backrest chairs with armrest for: Executive Office: 2. <b>See appendices figure 9.</b>	Nr	02		
10. Procure <b>Two (2) single black</b> seating leather chairs for the seating area. <b>See appendices figure 9.</b>	Nr	02		
<b>KITCHEN AREA</b>				
14. Procure <b>One (1)</b> double door <b>10 cu ft.</b> whirlpool standing fridge for the kitchen area. Colour to match the scheme in the kitchen.	Nr	01		
<b>17.*This item has been omitted. Please note that this item cannot be quoted and should not be used.*</b>				
<b>COMPUTERS</b>				
18. Procure and install 4 hp desktop computers of specification... <b>See appendices</b>	Nr	03		
<b>PROVISIONAL SUM b/f</b>				<b>\$10,000.00</b>
<b>Sub- Total b/f</b>				
<b>12.5 % Vat if Registered</b>				
<b>CONTRACT PRICE</b>				