



**TOBAGO HOUSE OF ASSEMBLY**  
**Division of Food Production, Forestry and Fisheries**  
**Montessori Trace, Glen Road**  
**Scarborough, Tobago**  
**TEL# (868) 639-5994/2234, 660-7152**  
**FAX (868) 639-1746**

## **AMENDMENT**

### **DFPFF 2019/20-0002 - INVITATION TO TENDER FOR**

### **REPAIR WORKS TO ROXBOROUGH FISHING FACILITY**

The following specs are to be added to the relevant work items at the aforementioned facility.

1. Allow for schedule 40 GI pipes to be used in the fencing works.
2. Allow for kaleidoscope brand of paint to be used in the painting works.
3. Contractors are to note that the Old Fishing Facility is be fenced in and therefore form part of the total 400 ft of fence work.
4. Contractors are to submit the amended Scope of Work in their tender submission package.

Please note that all other submission criteria remains the same as stated in the Tender document.

**APPENDIX A  
BILL OF QUANTITIES**

(This is document referred to in paragraph 13 of the pre – fixed Tender Submission Form)

**Name of Project: DFPPF 2019/20 – 0001 - Repairs works to Roxborough Fishing Facility**

**Contractor:** \_\_\_\_\_

**Project Brief:** The contractor shall supply all required expertise, labour, tools, equipment, material and services required to provide and complete this scope of work according to specification and standard set by the authorized agent of the Division. All unwanted concrete apparatus should be discarded from project site.

**Fill out the estimated cost in the Rate and Amount columns in accordance with the following Description, Unit and Quantity.**

**The scope of work is as follows:**

**Scope of Work  
REPAIR WORKS TO ROXBOROUGH FISHING FACILITY**

ITEM	DESCRIPTION	QTY.	UNIT	RATE	TOTAL
1	<b><u>Vending Area:</u></b>				
1.1	Cut concrete block partition as directed for the installation of 32" x 80" aluminum door.	1	nr.		
1.2	Supply and install 32" x 80" aluminum door complete with frame and locking device (door knob).	1	nr.		
1.3	Remove, supply and install double entry front door with aluminum doors (double). Allow for all ironmongery and locking device (door knob and dead bolt).	1	nr.		
1.4	Remove, supply and install 32" x 80" back door with aluminum door. Allow for all ironmongery and locking device (door knob and dead bolt).	1	nr.		
1.5	Remove and cart away existing tile from vending area, cold storage area and ice machine area.	986	sq ft		

1.6	Supply, lay and grout 17" x 17" ceramic floor tiles (non-skid) to the areas mentioned above. Note that approval must be obtained from the client regarding the type of tiles and pattern to be installed.	986	sq ft		
2	<b><u>Storage Room</u></b>				
2.1	Remove, supply and install double entry door with aluminum doors (double). Allow for all ironmongery and locking device (door knob and dead bolt).	1	nr.		
3	<b><u>Guard Boot</u></b>				
3.1	Remove, Supply and install 36" x 80" aluminum door complete with locking device (door knob).	1	nr.		
4	<b><u>Painting</u></b>				
4.1	Clean wall surfaces and apply two coats of <b>kaleidoscope</b> marine paint on all wall surfaces. Cater for similar colour to existing to be applied.	2,807	sq ft		
4.2	Strip existing paint and apply volkem 801 waterproofing to concrete roof area according to manufacturer's specification.	1,938	sq ft		
5	<b><u>External Works:</u></b>				
5.1	Supply and install plastic coated chain link fence attached to 2" galvanize line post and 4" corner post - set 10' apart, 12" below ground and 6' above ground coated with anti-corrosive paint. Also allow for 1 1/2" top, middle and bottom rails.	400	ft		
5.2	Fabricate and install 12' metal gate as directed. Catering for 2 inch galvanize <b>40 GI</b> pipe outer frame, 1/2" intermediate bars 4 inches apart and locking mechanism	72	sq ft		
6	<b><u>Clean site</u></b>				
6.1	Allow for the cleaning and disposal of all debris to an approve dump site		sum		
	<b>SUB TOTAL</b>				
	<b>VAT 12.5%</b>				
	<b>TOTAL</b>				

-END-

