

Item	Description	Qty	Unit	Rate	Amount
	A13 DESCRIPTION OF THE WORKS				
a	The work includes the construction of a change room and toilet facility.		Item	N/A	N/A
b	The structure is made of a reinforced concrete foundation and floor with a 6" rendered concrete block wall envelope and a wooden frame roof with 26 gauge prepainted roofing sheets.		Item	N/A	N/A
c	A20 The contract/ Subcontract Employer's insurance responsibility, workmen Compensations		Item		
d	A41 SITE ACCOMODATION. Site accommodation and sanitary facilities, fixed charge.		Item		
e	A42 Contractor's General Cost Items: Services and Facilities Provide the following Services and facilities:				
f	safety, health and welfare, fixed charge, as necessary to ensure protection to employees while working.		Item		
g	Rubbish disposal fixed charge throughout project		Item		
h	Power for the duration of the works, time related charge.		Item		
i	Potable water for the duration of the works, time related charge.				
j	A44 Contractor General cost items: Temporary Works Temporary works Access scaffolding, fixed charged, allowing access to high area of work		Item		
k	Fences hoardings The Contractor shall enclose the site 93m long of the work under construction with a hoarding 2400mm high consisting of galvanize sheets on 100 x 50mm timber post firmly secured at 1800mm centre with two 25mm x 100mm timber rails with access door for equipment. The Contractor is in addition required to take all precautions necessary for the safe custody of the works, materials, plant, public and Employer's property an the site.		Item		
	To summary				