



**Division of Food Production, Forestry and Fisheries  
Tobago House of Assembly  
Shirvan Administrative Complex  
Corner Milford and Shirvan Road, Tobago  
TEL# (868) 639-5994/2234, 660-7152  
FAX (868) 639-1746**

## **AMENDMENTS**

**DFPFF 20/21 – 006**

**Invitation to Tender  
For  
Access road Programme 2021**

**The following are the amendments made to the aforementioned tender.**

1. There were changes/ additional works to various **Work Packages (WP)** namely; **Work Package 1,2,3,5,6,7,8,12,13,15,16,17,18,20,26,28,29,30,32,33,34,35 and 36**. Such changes/ additional works were made in **RED** in the attached documents below.
2. Page 8, Submission Instructions (7) ( i)

- (i) **Pass performance** - signed pass performance appraisal (most recent) report from the Division's previous access road programme. *This requirement would be waived for new participants/contractors to the programme.*

3. Page 11 , Evaluation Criteria item (7) Equipment listing

7	Equipment Listing	Mandatory	Individuals/joint ventures must provide a listing of equipment and evidence of ownership. This include customs documentation/bill of sale/affidavit, insurance certificate, model type etc.  <b><i><u>For new participants only</u></i></b> , they are allowed to demonstrate a lease or rental agreement from the owners of the equipment (must demonstrate proof of ownership as stated above). If the equipment owner is bidding as an individual or as a joint venture, this agreement (lease or rental) <b><i><u>DOES NOT</u></i></b> disqualify the individual. It should be noted, equipment owners can have this agreement with <b><i><u>ONLY ONE OTHER</u></i></b> entity in the programme.
---	-------------------	-----------	------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

Please note all other submission criteria remains the same as stated in the tender document.

Attachment is submitted for your information and action.

Also attached is the statutory declaration forms with the corrected year.

Please be guided accordingly.

**WP 1**  
**BILL OF QUANTITIES**  
**Adelphi Branch Road to Belmont Branch Road Phase II**

Item	Description	Quantity	Unit	Rate	Total
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway 500' x 20'				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. Note that failure to put effective safety measures in place will result in a "stop work order".		sum		
	Total carried to summary				
<b>2.0</b>	<b>CONCRETE WORKS</b>				
2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation; align roadway etc.				
a)	Excavate and cart away top layer 500' x 20' x 150mm in depth	185	yds <sup>3</sup>		
b)	Allow for proper alignment of roadway		sum		
	Collection				
2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement –				

	6x6x5 gauge BRC, block work, weep holes and backfilling 10,000 ft <sup>2</sup>				
a)	Construct concrete roadway 500' x 20' x 6".	185	yds <sup>3</sup>		
b)	Slipper drain curb wall 2,133' x 6" x 8"	28	yds <sup>3</sup>		
c)	Slipper 4" thick x 12" wide	24	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	4	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
f)	Repair area between roadway and slipper drain with concrete finish, including any other areas along the roadway (with existing material) that is damaged by the contractor's operation in caring PRESENT works (all equipment included).		sum		
	Collection				
	Total carried to summary				
<b>3.0</b>	<b>DEMOBILIZE</b>				
3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				
a)	Allow for the removal of tools, equipment and unused materials offsite. Also include the removal of debris to an approved dump site		sum		
	Total carried to summary				
	<i>General Note</i>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore, this individual (supervisor) will be required to be onsite during project activities or at the				

	Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				

**WP 1**  
**BILL OF QUANTITIES**  
**Adelphi Branch Road to Belmont Branch Road Phase II**  
**Summary**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CONCRETE WORKS</b>	
3.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 2**  
**BILL OF QUANTITIES**  
**Poultry Farm Road, Argyle**

Item	Description	Quantity	Unit	Rate	Total
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway 1,000' x 16'				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. Note that failure to put effective safety measures in place will result in a "stop work order".		sum		
	Total carried to summary				
<b>2.0</b>	<b>CHIP SEAL WORKS</b>				
2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation; align roadway etc.				
a)	Excavate and cart away top layer 12 inches in depth	593	yds <sup>3</sup>		
b)	Allow for alignment of roadway as identified/directed		sum		
c)	Allow for sub-base construction 300mm with imported backfill material (rotten rock) compacted in 3" layer to 97% MPD	593	yds <sup>3</sup>		

d)	Subsequent to excavating roadway, install 20ft length, 6 inch perforated PVC pipes, 3 ft in depth from existing ground level, perpendicular to roadway. Allow for no less than 600mm over hang in open drain. Further allow for pipe protection with geo-fabric and 6 inch cover around with crush-run.	2	nr		
	Collection				
2.2	All inclusive of Crush Run, spread and compacted with 5 to 10 tonne roller in layers of 3" to finish at 6" thick; 2mm aggregate; application of bitumen to crush run and 2mm aggregate				
a)	Road base construction using crushed run, supply, spread and compact in 3" layer to 98% MPD and apply bitumen to crush run	16,016	ft2		
b)	Supply and spread 2mm aggregate and apply bitumen to seal coat roadway	16,016	ft2		
	Collection				
	Total carried to summary				
<b>3.0</b>	<b>CONCRETE WORKS</b>				
3.1	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling where necessary.				
a)	Construct three (6 ft x 16ft wide x 5") V-drain	4.3	yds <sup>3</sup>		
b)	Construct curb wall 1,000' x 6" x 8"	13	yds <sup>3</sup>		
c)	Slipper 4" thick x 12" wide	11	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	2	m3		



e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
	Total carried to summary				
<b>4.0</b>	<b>DEMOBILIZE</b>				
3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				
a)	Allow for the removal of tools, equipment and unused materials offsite. Also include the removal of debris to an approved dump site		sum		
	Total carried to summary				
	<i>General Note</i>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore, this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				

**WP 2**  
**BILL OF QUANTITIES**  
**Poultry Farm Road, Argyle**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CHIP SEAL WORKS</b>	
3.0	<b>CONCRETE WORKS</b>	
4.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 3**  
**BILL OF QUANTITIES**  
**Ballington Trace, Drainage and Crossings, Good Wood**

Item	Description	Quantity	Unit	Rate	Total
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. Note that failure to put effective safety measures in place will result in a "stop work order".		sum		
d)	Allow for the removal of vegetation from work area.		sum		
	Total carried to summary				
<b>2.0</b>	<b>CONCRETE WORKS</b>				
2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation; align roadway etc.				
a)	Excavate and cart away top layer 475' x 12' x 150mm in depth	106	yds <sup>3</sup>		

b)	Allow for proper alignment of roadway		sum		
	Collection				
2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling 3,600 ft <sup>2</sup>				
a)	Construct concrete roadway 300' x 12' x 6"	67	yds <sup>3</sup>		
b)	Construct curb wall 300' x 6" x 8"	4	yds <sup>3</sup>		
c)	Construct 4" thick x 12" wide slipper	3	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	0.6	yds <sup>3</sup>		
e)	<del>Allow for backfilling behind 8" curb wall and existing ground with rotten rock –delete this item</del>		sum		
f)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
g)	Supply and place 1/2" corrugated steel 8" c/c at dry gully area as directed (to cover 6'x12' area)	14	lgh		
	Collection				
2.3	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling for roadway 2,100 ft <sup>2</sup>				
a)	Construct concrete roadway 175' x 12' x 6"	39	yds <sup>3</sup>		
b)	Construct curb wall 175' x 6" x 8"	2	yds <sup>3</sup>		
c)	Slipper 4"x12" Slipper	2	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	0.3	yds <sup>3</sup>		
	Collection				

2.4	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 5/8 and 1/2 corrugated steel 8” c/c in both direction, weep holes and backfilling material				
a)	Construct reinforce concrete box drain with 4” thick base – 1,100 ft long x 2 ft wide x 2 ft depth (internal dimension) – reinforcement 1/2” corrugated steel at 8” c/c. All wall to be 150mm thick and render on open faces. Also allow for backfill behind box drain (rotten rock)		sum		
b)	Construct reinforce concrete crossing 14’ feet x 4’ feet 4” inches x 6” thick over box drain. 5/8” corrugated steel (both ways) to be placed 8” c/c		sum		
c)	Allow for backfilling (rotten rock) and compaction of existing 1,100 ft earthen drain to arrive at new formation level		sum		
	Collection				
	Total carried to summary				
<b>3.0</b>	<b>DEMOBILIZE</b>				
3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				
a)	Allow for the removal of tools, equipment and unused materials offsite. Also include for the removal of debris to an approved dump site		sum		
	Total carried to summary				
	<b>General Note</b>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore, this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				

2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				

**WP 3**  
**BILL OF QUANTITIES**  
**Ballington Trace, Drainage and Crossings, Good Wood**  
**Summary**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CONCRETE WORKS</b>	
3.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 5**  
**BILL OF QUANTITIES**  
**Belmont Farm Main Road Phase I**

Item	Description	Quantity	Unit	Rate	Total
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. Note that failure to put effective safety measures in place will result in a "stop work order".		sum		
	Total carried to summary				
<b>2.0</b>	<b>CONCRETE WORKS</b>				
2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation; align roadway etc.				
a)	Allow for the removal of vegetation from the roadway/ <del>project area</del>		sum		
b)	<del>Allow for the removal of loose material and compact roadway with 10 tonne roller to 97% MPD</del>	262	<del>sum</del>		

	Excavate and cart away top layer 150mm in dept		yds <sup>3</sup>		
c)	Allow for alignment of roadway as identified/directed		sum		
	Collection				
2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling 14,140 ft <sup>2</sup>				
a)	Construct concrete roadway 707' x 20' x 6".	262	yds <sup>3</sup>		
b)	Construct curb wall 707' x 6" x 8"	9	yds <sup>3</sup>		
c)	Construct 4" thick x 12" wide slipper	8	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	1.3	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
f)	Allow for the placing of 4" PVC sleeves with end caps every 300 feet under R/C roadway (perpendicular to roadway)	70	ft		
	Collection				
2.3	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling for roadway 2,400 ft <sup>2</sup>				
a)	Construct concrete roadway 200' x 12' x 6"	45	yds <sup>3</sup>		
b)	Construct curb wall 200' x 6" x 8"	3	yds <sup>3</sup>		
c)	Slipper 4"x12" Slipper	2	yds <sup>3</sup>		



d)	Render outer face and top of curb wall	1	yds <sup>3</sup>		
e)	Allow for backfilling behind 8" curb wall and existing ground with rotten rock		sum		
	Collection				
	Total carried to summary				
<b>3.0</b>	<b>DEMOBILIZE</b>				
3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				
a)	Allow for the removal of tools, equipment and unused materials offsite. Also include the removal of debris to an approved dump site		sum		
	Total carried to summary				
	<b>General Note</b>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore, this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				

**WP 5**  
**BILL OF QUANTITIES**  
**Belmont Farm Main Road Phase I**  
**Summary**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CONCRETE WORKS</b>	
3.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 6**  
**BILL OF QUANTITIES**  
**Belmont Farm Main Road Phase II**

<b>Item</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Total</b>
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway 801ft x 20ft				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. Note that failure to put effective safety measures in place will result in a "stop work order".		sum		
	Total carried to summary				
<b>2.0</b>	<b>CONCRETE WORKS</b>				
2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation; align roadway etc.				
a)	Allow for the removal of vegetation from the roadway		sum		

b)	<del>Allow for the removal of loose material and compact roadway with 10 tonne roller to 97% MPD</del> Excavate and cart away top layer 150mm in depth	297	sum yds <sup>3</sup>		
c)	Allow for alignment of roadway as identified/ directed		sum		
	Collection				
2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling 16,020 ft <sup>2</sup>				
a)	Construct concrete roadway 801' x 20' x 6".	297	yds <sup>3</sup>		
b)	Slipper drain curb wall 801' x 6" x 8"	10	yds <sup>3</sup>		
c)	Slipper 4" thick x 12" wide	9	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	2	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
f)	Allow for the placing of 4" PVC sleeves with end caps every 300 feet under R/C roadway (perpendicular to roadway)	90	ft		
	Collection				
	Total carried to summary				
<b>3.0</b>	<b>DEMOBILIZE</b>				
3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				
a)	Allow for the removal of tools, equipment and unused materials offsite. Also include the removal of debris to an approved dump site		sum		

	Total carried to summary				
	<b>General Note</b>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore, this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				

**WP 6**  
**BILL OF QUANTITIES**  
**Belmont Farm Main Road Phase II**  
**Summary**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CONCRETE WORKS</b>	
3.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 7**  
**BILL OF QUANTITIES**  
**Belmont Farm Development Main Road Phase III**

Item	Description	Quantity	Unit	Rate	Total
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway 693ft x 20ft				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. <ul style="list-style-type: none"> <li>Note that failure to put effective safety measures in place will result in a "stop work order".</li> </ul>		sum		
	Total carried to summary				
<b>2.0</b>	<b>CONCRETE WORKS</b>				
2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation; align roadway etc.				
a)	Allow for the removal of vegetation from the roadway		sum		
b)	<del>Allow for the removal of loose material and compact roadway with 10 tonne roller to 97% MPD</del> Excavate and cart away top layer 150mm in depth	257	sum yds <sup>3</sup>		
c)	<del>Allow for alignment of roadway as identified/ directed</del>		sum		

	Collection				
2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling 13,860 ft <sup>2</sup>				
a)	Construct concrete roadway 693' x 20' x 6".	257	yds <sup>3</sup>		
b)	Slipper drain curb wall 693' x 6" x 8"	9	yds <sup>3</sup>		
c)	Slipper 4" thick x 12" wide	8	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	1	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
f)	Allow for the placing of 4" PVC sleeves with end caps every 300 feet under R/C roadway (perpendicular to roadway)	70	ft		
	Collection				
2.3	All inclusive of excavation, formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 5/8 corrugated steel 8" c/c in both direction				
a)	Allow for the supply and installation of 20' x 5' HDPE pipe. In addition, allow for its encasement in 6" reinforce concrete all round (1/2" HT rebar at 8" c/c).		sum		
b)	Construct catch pit 3'x5'x5' - 150mm thick - 1/2" HT rebar at 8" c/c				
c)	Allow for backfilling behind pipe (rotten rock) on completion of concrete works		sum		
	Collection				
	Total carried to summary				
<b>3.0</b>	<b>DEMOBILIZE</b>				
3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				



a)	Allow for the removal of tools, equipment and unused materials offsite. Also include the removal of debris to an approved dump site		sum		
	Total carried to summary				
	<b>General Note</b>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore, this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				

**WP 7**  
**BILL OF QUANTITIES**  
**Belmont Farm Main Road Phase III**  
**Summary**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CONCRETE WORKS</b>	
3.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 8**  
**BILL OF QUANTITIES**  
**Belmont Farm Main Road Phase IV**

Item	Description	Quantity	Unit	Rate	Total
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway 570ft x 20ft				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. Note that failure to put effective safety measures in place will result in a "stop work order".		sum		
	Total carried to summary				
<b>2.0</b>	<b>CONCRETE WORKS</b>				
2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation; align roadway etc.				
a)	Allow for the removal of vegetation from the roadway		sum		
b)	<del>Allow for the removal of loose material and compact roadway with 10 tonne roller to 97% MPD</del> Excavate and cart away top layer 150mm in depth	211	<del>sum</del> yds <sup>3</sup>		

c)	Allow for alignment of roadway as identified/ directed		sum		
	Collection				
2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling 11,400 ft <sup>2</sup>				
a)	Construct concrete roadway 570' x 20' x 6".	211	yds <sup>3</sup>		
b)	Slipper drain curb wall 570' x 6" x 8"	7	yds <sup>3</sup>		
c)	Slipper 4" thick x 12" wide	6	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	1	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
f)	Allow for the placing of 4" PVC sleeves with end caps every 300 feet under R/C roadway (perpendicular to roadway)	60	ft		
	Collection				
	Total carried to summary				
<b>3.0</b>	<b>DEMOBILIZE</b>				
3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				
a)	Allow for the removal of tools, equipment and unused materials offsite. Also include the removal of debris to an approved dump site		sum		
	Total carried to summary				
	<b>General Note</b>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore,				

	this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				

**WP 8**  
**BILL OF QUANTITIES**  
**Belmont Farm Main Road Phase IV**  
**Summary**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CONCRETE WORKS</b>	
3.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 12**  
**BILL OF QUANTITIES**  
**Caledonia Farm Road to Money Hill Phase III**

Item	Description	Quantity	Unit	Rate	Total
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway <del>1,000ft x 19ft</del> 1,300 ft x 19 ft				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. Note that failure to put effective safety measures in place will result in a "stop work order".		sum		
	Total carried to summary				
<b>2.0</b>	<b>CONCRETE WORKS</b>				
2.1	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 1/2 corrugated steel 10” c/c in both direction				
a)	Construct reinforce concrete box drain 600’ long x 2’ wide x 2’ depth (internal dimension). All wall to be 150mm thick.	600	ft		
b)	Allow for backfilling (rotten rock) behind 8” curb wall and general landscaping along roadway		sum		
	Total carried to summary				

<b>3.0</b>	<b>EARTHEN SURFACE</b>				
3.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation and alignment for roadway <del>19,000 ft<sup>2</sup></del> – 24,700 ft <sup>2</sup>				
a)	Excavate and cart away top layer one foot (12 inches) in depth	<del>704</del> 915	yds <sup>3</sup>		
b)	Allow for proper alignment of roadway		sum		
c)	Supply and place rotten rock, compacted in 3" layer to 97% MPD	<del>704</del> 915	yds <sup>3</sup>		
	Collection				
	Total carried to summary				
<b>4.0</b>	<b>DEMOBILIZE</b>				
3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				
a)	Allow for the removal of tools, equipment and unused materials offsite. Also include the removal of debris to an approved dump site		sum		
	Total carried to summary				
	<b>General Note</b>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore, this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the				



	Project Implementation Unit for review prior to the commencement of works.				
--	----------------------------------------------------------------------------	--	--	--	--

**WP 12**  
**BILL OF QUANTITIES**  
**Caledonia Farm Road to Money Hill Phase III**  
**Summary**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CONCRETE WORKS</b>	
3.0	<b>EARTHEN SURFACE</b>	
4.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 13**  
**BILL OF QUANTITIES**  
**Charlottesville Breeding Unit and Nicholson Drive, Observatory Road, Charlottesville**

Item	Description	Quantity	Unit	Rate	Total
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. Note that failure to put effective safety measures in place will result in a "stop work order".		sum		
	Total carried to summary				
<b>2.0</b>	<b>CONCRETE WORKS</b> (Charlottesville Breeding Unit)				
2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation; align roadway etc.				
a)	Excavate and cart away top layer 260' x 10' x 150mm in depth	48	yds <sup>3</sup>		
b)	Allow for alignment of roadway as identified/directed		sum		

	Collection				
2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling for roadway 2,600 ft <sup>2</sup>				
a)	Construct concrete roadway 260' x 10 x 150mm.	48	yds <sup>3</sup>		
b)	Slipper drain curb wall 260' x 6" x 8"	3	yds <sup>3</sup>		
c)	Slipper 4" thick x 12" wide	3	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	0.5	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
2.3	Make good the area between office building and toilet - cast 4" thick concrete walkway (18' x 25') as directed.	5	yds <sup>3</sup>		
2.4	Make good the area above the <del>toilet</del> the sheep/ goat pens as directed – then construct 15' x 4' reinforce concrete tank stand 1 foot above existing ground level. In addition, allow for:  12" x 12" Ground beams externally and one tie beam midspan; 5/8" corrugated main bars, 3/8" binders at 8" c/c surrounded with 1 1/2" inches concrete cover.  8" x 8" x 16" blockwork atop ground beams with 1/2" corrugated bars (vertical) at 16" c/c and void fill with rotten rock (compacted).  6x6x5 gauge BRC; 4" thick concrete base; external concrete, rendered on outer face.	60	sq ft		
2.5	Construct 30' x 7' high retaining wall next to toilet. Allow for:  2' wide x 1' thick concrete base two feet below ground, 5/8" corrugated steel in both direction (mat finish); 5/8" HT vertical bars in	210	sq ft		

	every other block core (16" c/c) – block 8" x 8" x 16"; all block core filled with weak concrete mix, and render on outer face.				
	Total carried to summary				
<b>2.6</b>	<b>CONCRETE WORKS</b> <i>(Nicholson Drive, Observatory Road)</i>				
2.6.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation; align roadway etc.				
a)	Excavate and cart away top layer 465' x 12' x 150mm in depth	103	yds <sup>3</sup>		
b)	Allow for alignment of roadway as identified/directed		sum		
	Collection				
2.6.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling 5,580 ft <sup>2</sup>				
a)	Construct concrete roadway 465' x 12' x 6".	103	yds <sup>3</sup>		
b)	Slipper drain curb wall 465' x 6" x 8"	6	yds <sup>3</sup>		
c)	Slipper 4" thick x 12" wide	5	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	1	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
	Collection				
	Total carried to summary				
<b>3.0</b>	<b>DEMOBILIZE</b>				

3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				
a)	Allow for the removal of tools, equipment and unused materials offsite. Also include the removal of debris to an approved dump site		sum		
	Total carried to summary				
	<b>General Note</b>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore, this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				

**WP 13**  
**BILL OF QUANTITIES**  
**Charlottesville Breeding Unit and Nicholson Drive, Observatory Road, Charlottesville**  
**Summary**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CONCRETE WORKS</b> <i>(Charlottesville Breeding Unit)</i>	
2.6	<b>CONCRETE WORKS</b> <i>(Nicholson Drive, Observatory Road)</i>	
3.0	<b>DEMobilIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 15**  
**BILL OF QUANTITIES**  
**Connector Road (LEFT) Belmont Farm Road Phase I**

Item	Description	Quantity	Unit	Rate	Total
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway 500ft x 20ft				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. <ul style="list-style-type: none"> <li>Note that failure to put effective safety measures in place will result in a "stop work order".</li> </ul>		sum		
	Total carried to summary				
<b>2.0</b>	<b>CONCRETE WORKS</b>				
2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation; align roadway etc.				
a)	<del>Allow for the removal of loose material and compact roadway with 10 tonne roller to 97% MPD</del> Excavate and cart away top layer 150mm in depth	185	<del>sum</del> yds <sup>3</sup>		
b)	<del>Allow for alignment of roadway as identified/directed</del>		sum		
	Collection				



2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling 10,000 ft <sup>2</sup>				
a)	Construct concrete roadway 500' x 20' x 6".	185	yds <sup>3</sup>		
b)	Slipper drain curb wall 500' x 6" x 8"	7	yds <sup>3</sup>		
c)	Slipper 4" thick x 12" wide	6	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	1	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
e)	Allow for the placing of 4" PVC sleeves with end caps every 300 feet under R/C roadway (perpendicular to roadway)	60	ft		
	Collection				
2.3	All inclusive of excavation, formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 5/8 corrugated steel 8" c/c in both direction				
a)	Allow for the supply and installation of 20' x 5' HDPE pipe. In addition, allow for its encasement in 6" reinforce concrete all round (1/2" HT rebar at 8" c/c).		sum		
b)	Construct catch pit 3'x5'x5' - 150mm thick - 1/2" HT rebar at 8" c/c		sum		
c)	Allow for backfilling on both sides of crossing (rotten rock) on completion of concrete works		sum		
	Collection				
	Total carried to summary				
<b>3.0</b>	<b>DEMobilize</b>				

3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				
a)	Allow for the removal of tools, equipment and unused materials offsite. Also include the removal of debris to an approved dump site		sum		
	Total carried to summary				
	<b>General Note</b>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore, this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				

**WP 15**  
**BILL OF QUANTITIES**  
**Connector Road (LEFT) - Belmont Farm Road Phase I**  
**Summary**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CONCRETE WORKS</b>	
3.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 16**  
**BILL OF QUANTITIES**  
**Connector Road (LEFT) - Belmont Farm Road Phase II**

Item	Description	Quantity	Unit	Rate	Total
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway 537ft x 20ft				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPPF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. Note that failure to put effective safety measures in place will result in a "stop work order".		sum		
	Total carried to summary				
<b>2.0</b>	<b>CONCRETE WORKS</b>				
2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation; align roadway etc.				
a)	<del>Allow for the removal of loose material and compact roadway with 10 tonne roller to 97% MPD</del> Excavate and cart away top layer 150mm in depth	200	sum yds <sup>3</sup>		
b)	<del>Allow for alignment of roadway as identified/ directed</del>		sum		

	Collection				
2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling 10,740 ft <sup>2</sup>				
a)	Construct concrete roadway 537' x 20' x 6".	200	yds <sup>3</sup>		
b)	Slipper drain curb wall 537' x 6" x 8"	7	yds <sup>3</sup>		
c)	Slipper 4" thick x 12" wide	6	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	1	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
f)	Allow for the placing of 4" PVC sleeves with end caps every 300 feet under R/C roadway (perpendicular to roadway)	60	ft		
f)	Construct R/C turntable – radius 7ft x 6" thick	3	yds <sup>3</sup>		
	Collection				
	Total carried to summary				
<b>3.0</b>	<b>DEMOBILIZE</b>				
3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				
a)	Allow for the removal of tools, equipment and unused materials offsite. Also include the removal of debris to an approved dump site				
	Total carried to summary				
	<b>General Note</b>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore,				

	this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				

**WP 16**  
**BILL OF QUANTITIES**  
**Connector Road (LEFT) - Belmont Farm Road Phase II**  
**Summary**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CONCRETE WORKS</b>	
3.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 17**  
**BILL OF QUANTITIES**  
**Connector Road (RIGHT) - Belmont Farm Road Phase I**

Item	Description	Quantity	Unit	Rate	Total
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway 716ft x 20ft				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPPF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. <ul style="list-style-type: none"> <li>Note that failure to put effective safety measures in place will result in a "stop work order".</li> </ul>		sum		
	Total carried to summary				
<b>2.0</b>	<b>CONCRETE WORKS</b>				
2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation; align roadway etc.				
a)	<del>Allow for the removal of loose material and compact roadway with 10 tonne roller to 97% MPD</del> Excavate and cart away top layer 150mm in depth	265	<del>sum</del> yds <sup>3</sup>		
b)	<del>Allow for alignment of roadway as identified/directed</del>		sum		



	Collection				
2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling 14,320 ft <sup>2</sup>				
a)	Construct concrete roadway 716' x 20' x 6".	265	yds <sup>3</sup>		
b)	Slipper drain curb wall 716' x 6" x 8"	9	yds <sup>3</sup>		
c)	Slipper 4" thick x 12" wide	8	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	1	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
f)	Allow for the placing of 4" PVC sleeves with end caps every 300 feet under R/C roadway (perpendicular to roadway)	60	ft		
	Collection				
	Total carried to summary				
<b>3.0</b>	<b>DEMOBILIZE</b>				
3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				
a)	Allow for the removal of tools, equipment and unused materials offsite. Also include the removal of debris to an approved dump site		sum		
	Total carried to summary				
	<b>General Note</b>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore,				

	this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				

**WP 17**  
**BILL OF QUANTITIES**  
**Connector Road (RIGHT) - Belmont Farm Road Phase I**  
**Summary**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CONCRETE WORKS</b>	
3.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 18**  
**BILL OF QUANTITIES**  
**Connector Road (RIGHT) Belmont Farm Road Phase II**

Item	Description	Quantity	Unit	Rate	Total
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway 577ft x 20ft				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. Note that failure to put effective safety measures in place will result in a "stop work order".		sum		
	Total carried to summary				
<b>2.0</b>	<b>CONCRETE WORKS</b>				
2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation; align roadway etc.				
a)	<del>Allow for the removal of loose material and compact roadway with 10 tonne roller to 97% MPD</del> Excavate and cart away top layer 150mm in depth	213	yds <sup>3</sup>		
b)	<del>Allow for alignment of roadway as identified/directed</del>		sum		

	Collection				
2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling 11,540 ft <sup>2</sup>				
a)	Construct concrete roadway 577' x 20' x 6".	213	yds <sup>3</sup>		
b)	Slipper drain curb wall 577' x 6" x 8"	7	yds <sup>3</sup>		
c)	Slipper drain 4" thick x 12" wide	6	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	1	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
f)	Allow for the placing of 4" PVC sleeves with end caps every 300 feet under R/C roadway (perpendicular to roadway)	60	ft		
	Collection				
2.3	All inclusive of excavation, formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 5/8 corrugated steel 8" c/c in both direction				
a)	Allow for the supply and installation of 20' x 5' HDPE pipe. In addition, allow for its encasement in 4" thick base and 8" thick concrete side walls – also cater for the installation of wing walls on both ends		sum		
b)	Allow for backfilling on compaction with rotten rock between roadway and concrete walls		sum		
	Collection				
	Total carried to summary				
<b>3.0</b>	<b>DEMOBILIZE</b>				

3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				
a)	Allow for the removal of tools, equipment and unused materials offsite. Also include the removal of debris to an approved dump site		sum		
	Total carried to summary				
	<b>General Note</b>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore, this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				

**WP 18**  
**BILL OF QUANTITIES**  
**Connector Road (RIGHT) Belmont Farm Road Phase II**  
**Summary**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CONCRETE WORKS</b>	
3.0	<b>DEMobilIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 20**  
**BILL OF QUANTITIES**  
**Connector Road to Castara Road, Mt. St. George**

Item	Description	Quantity	Unit	Rate	Total
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway 200' x 14'				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. Note that failure to put effective safety measures in place will result in a "stop work order".		sum		
	Total carried to summary				
<b>2.0</b>	<b>CONCRETE <del>WORKS</del> ROADWAY</b>				
2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation; align roadway etc.				
a)	Excavate and cart away top layer 200' x 14' x 150mm in dept	52	yds <sup>3</sup>		
b)	Allow for alignment of roadway as identified/directed		sum		
	Collection				



2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling 2,800 ft2				
a)	Construct concrete roadway 200' x 14' x 6".	52	yds <sup>3</sup>		
b)	Slipper drain curb wall 200' x 6" x 8"	3	yds <sup>3</sup>		
c)	Slipper 4" thick x 12" wide	3	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	2	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
	Collection				
	Total carried to summary				
2.3	<b>RETAINING WALL - 70ft x 8 ins thick x 12ft high</b>				
	<b>EXCAVATION AND EARTH WORKS</b>				
	All inclusive of good working equipment - backhoe, dump truck, compactor; remove vegetation and loose earth; set out trench etc.				
a)	Clear site of spoils and dispose in appropriate manner		sum		
b)	Allow for excavation of trench not exceeding 36" deep		sum		
	Total carried to summary				
2.3.1	<b>REINFORCEMENT WORK</b>				
	All inclusive of good working equipment – generator, chop saw, nippers; reinforcement – 5/8" HT rebar 2" concrete cover all round				
a)	Supply and place 5/8" HT steel in retaining wall footing (mat design – 69' 8" x 2' 8" - rebar 12" c/c for vertical pieces and 8" c/c for	764	kg		

	horizontal pieces. Allow for stem reinforcement to flow continuously from mat into stem/ wall.				
b)	Supply and place 5/8" HT steel (lace) 9" c/c to retaining wall stem	518	kg		
	Total carried to summary				
2.3.2	<b>CONCRETE WORKS</b>				
	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, weep holes, perforated pipe, geo-fabric and backfilling material.				
a)	Supply and pour 21KN/mm2 concrete to retaining wall footing and stem	31	yds <sup>3</sup>		
b)	Allow for 2" PVC weeper holes 3ft c/c		sum		
c)	Supply and place 6" PVC perforated pipe to back of retaining wall	4	lgh		
d)	Allow for 1" to 1 1/2" gravel backfill to height of retaining wall. Also allow for supply and placing of geo fabric		sum		
e)	Allow for repair works between existing roadway and the retaining wall with concrete mix		sum		
	Collection				
	Total carried to summary				
3.0	<b>DEMOBILIZE</b>				
3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				
a)	Allow for the removal of tools, equipment and unused materials offsite. Also include the removal of debris to an approved dump site		sum		
	Total carried to summary				

	<b>General Note</b>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore, this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				

**WP 20**  
**BILL OF QUANTITIES**  
**Connector Road to Castara Road, Mt. St. George**  
**Summary**

Item	Description	Total
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CONCRETE <del>WORKS ROADWAY</del></b>	
2.3	<b>RETAINING WALL</b>	
3.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 24**  
**BILL OF QUANTITIES**  
**Goldsborough Estate Roads**

<b>Item</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Total</b>
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. Note that failure to put effective safety measures in place will result in a "stop work order".		sum		
	Total carried to summary				
<b>2.0</b>	<b>CONCRETE WORKS</b>				
2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation; align roadway etc.				
a)	Excavate and cart away top layer 540' x 14' x 150mm in depth	140	yds <sup>3</sup>		
b)	Allow for alignment of roadway as identified/directed		sum		

	Collection				
2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling 7,560 ft2				
a)	Construct concrete roadway 540' x 14' x 6"	140	yds <sup>3</sup>		
b)	Construct curb wall 540' x 6" x 8"	7	yds <sup>3</sup>		
c)	Construct 4" thick x 12" wide slipper	6	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	1	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
	Collection				
2.3	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 1/2 corrugated steel 8" c/c in both direction				
a)	Construct reinforce concrete slab covered box drain. Box drain with 4" thick base - 14' long 4' wide x 4' depth (internal dimension) – reinforcement 5/8" corrugated steel at 10" c/c. Slab cover to be 14 ft long x 5 ft 4 inches wide x 6 inches depth single layer 5/8" mat (both directions). All wall to be 150mm thick.		sum		
b)	Construct concrete V-drain along roadway 14 ft long x 20 ft wide x 150mm thick	6	nr		
	Collection				
	Total carried to summary				
<b>3.0</b>	<b>EARTHEN SURFACE</b>				
3.1	All inclusive of good working equipment - excavator, dump truck, 10 tonne roller compactor for excavation works; remove vegetation and align roadway 20,000 ft2				

a)	Excavate and cart away top layer 1,000 ft long x 20 ft wide x 12 inches in dept	740	yds <sup>3</sup>		
b)	Allow for alignment of roadway as identified/directed		sum		
c)	Supply and place rotten rock, compacted in 3" layer to 97% MPD	740	yds <sup>3</sup>		
d)	Construct R/C curb wall 1,000' x 6" x 8"	13	yds <sup>3</sup>		
e)	Construct R/C 4" thick x 12" wide slipper	11	yds <sup>3</sup>		
f)	Render outer face and top of curb wall	2	yds <sup>3</sup>		
g)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
	Collection				
3.2	All inclusive of good working equipment - excavator, dump truck, 10 tonne roller compactor for excavation works; remove vegetation and align roadway 14,400 ft <sup>2</sup>				
a)	Excavate and cart away top layer 1,200 ft long x 14 ft wide x 12 inches in depth	622	yds <sup>3</sup>		
b)	Allow for alignment of roadway as identified/directed		sum		
c)	Supply and place rotten rock, compacted in 3" layer to 97% MPD	622	yds <sup>3</sup>		
	Collection				
	Total carried to summary				
<b>4.0</b>	<b>DEMOBILIZE</b>				
3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				

a)	Allow for the removal of tools, equipment and unused materials offsite. Also include for the removal of debris to an approved dump site		sum		
	Total carried to summary				
	<b>General Note</b>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore, this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				



**WP 24**  
**BILL OF QUANTITIES**  
**Goldsborough Estate Roads**  
**Summary**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>GENERAL</b>	
2.0	<b>CONCRETE WORKS</b>	
3.0	<b>EARTHEN SURFACE</b>	
4.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 26**  
**BILL OF QUANTITIES**  
**Grenadian Hill Connector Road Belle Garden**

<b>Item</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Total</b>
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. Note that failure to put effective safety measures in place will result in a "stop work order".		sum		
	Total carried to summary				
<b>2.0</b>	<b>CONCRETE WORKS</b> (Upper Grenadian Hill)				
2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation; align roadway etc.				
a)	Excavate and cart away top layer 400' x 18' x 150mm in depth	133	yds <sup>3</sup>		

b)	Allow for alignment of roadway as identified/ directed		sum		
	Collection				
2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling 7,200 ft <sup>2</sup>				
a)	Construct concrete roadway 400' x 18' x 6".	133	yds <sup>3</sup>		
b)	Slipper drain curb wall 400' x 6" x 8"	5	yds <sup>3</sup>		
c)	Slipper 4" thick x 12" wide	4	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	0.7	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
f)	Construct catch-pit 2'x2'x2' (internal dimensions) as directed. Cater for 4" concrete base	1	nr		
g)	Allow for the installation of 4" PVC pipe – 4ft above ground – 3ft apart filled with concrete along road edge as directed.		allow		
	Collection				
<b>2.3</b>	<b>CONCRETE WORKS - Continues</b> (Lower Grenadian Hill)				
2.3.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation; align roadway etc.				
a)	Excavate and cart away top layer 368' x 17' x 150mm in depth	116	yds <sup>3</sup>		
b)	Allow for alignment of roadway as identified/ directed		sum		
	Collection				

2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling 6,624 ft2				
a)	Construct concrete roadway 368' x 17' x 6".	116	yds <sup>3</sup>		
b)	Slipper drain curb wall 368' x 6" x 8"	5	yds <sup>3</sup>		
c)	Slipper 4" thick x 12" wide	4	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	0.7	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
f)	Allow for the installation of 4" PVC pipe – 4ft above ground – 3ft apart filled with concrete along road edge as directed.		allow		
	Collection				
	Total carried to summary				
<b>3.0</b>	<b>EARTHEN SURFACE</b>				
	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); alignment of turntable 25' diameter				
a)	Excavate and cart away top layer 6 inches in depth	9	yds <sup>3</sup>		
b)	Allow for alignment of turntable (25' dia.)		sum		
c)	Supply and place rotten rock, and compact in 3" layer to 97% MPD	9	yds <sup>3</sup>		
	Total carried to summary				
<b>3.0</b>					
<b>4.0</b>	<b>DEMOBILIZE</b>				
3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				

a)	Allow for the removal of tools, equipment and unused materials offsite. Also include the removal of debris to an approved dump site		sum		
	Total carried to summary				
	<b>General Note</b>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore, this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				

**WP 26**  
**BILL OF QUANTITIES**  
**Grenadian Hill Connector Road Belle Garden**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CONCRETE WORKS</b>	
3.0	<b>EARTHEN SURFACE</b>	
4.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 28**  
**BILL OF QUANTITIES**  
**Robert Street Extension, Roxborough Phase II**

<b>Item</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Total</b>
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway 539' x 17'				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. Note that failure to put effective safety measures in place will result in a "stop work order".		sum		
	Total carried to summary				
<b>2.0</b>	<b>CONCRETE WORKS</b>				
2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation; align roadway etc.				

a)	Excavate and cart away top layer 281' x 17' x 150mm in dept	88	yds <sup>3</sup>		
b)	Allow for compaction of roadway with 10 tonne roller to 97% MPD after crossing		sum		
	Collection				
2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling 9,163 ft2				
a)	Construct concrete roadway 539' x 17' x 6".	170	yds <sup>3</sup>		
b)	Slipper drain curb wall 539' x 6" x 8"	7	yds <sup>3</sup>		
c)	Slipper 4" thick x 12" wide	6	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	1	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
f)	Allow for (6 ft x 17ft wide x 6") V-drain during concrete works		sum		
g)	Allow for the fixing and placing of concrete to roadway entrance 12ft x 6ft. Note that the construction is to be similar to that of the roadway.		sum		
h)	Allow for turntable (25' dia.) as directed. Note that the construction is to be similar to that of the roadway.		sum		
	Collection				
	Total carried to summary				
<b>3.0</b>	<b>DEMOBILIZE</b>				
3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				



a)	Allow for the removal of tools, equipment and unused materials offsite. Also include the removal of debris to an approved dump site		sum		
	Total carried to summary				
	<b>General Note</b>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore, this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				

**WP 28**  
**BILL OF QUANTITIES**  
**Robert Street Extension, Roxborough Phase II**  
**Summary**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CONCRETE WORKS</b>	
3.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 29**  
**BILL OF QUANTITIES**  
**Robinson Trace Louis D'oir Drainage and Concrete Platform**

Item	Description	Quantity	Unit	Rate	Total
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. Note that failure to put effective safety measures in place will result in a "stop work order".		sum		
	Total carried to summary				
<b>2.0</b>	<b>CONCRETE WORKS</b>				

a)	Construct reinforce concrete box drain with 4" thick base – 300 ft long x 2 ft wide x <del>2-ft</del> 3ft depth (internal dimension) – reinforcement 1/2" corrugated steel at 8" c/c. All wall to be 150mm thick and render on open face		sum		
	Collection				
b)	Construct R/C concrete platform	1,800	sq ft		
d)	Allow for backfilling (rotten rock) box drain and general landscaping of the works		sum		
	Collection				
	Total carried to summary				
<b>3.0</b>	<b>DEMOBILIZE</b>				
3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				
a)	Allow for the removal of tools, equipment and unused materials offsite. Also include for the removal of debris to an approved dump site		sum		
	Total carried to summary				
	<b>General Note</b>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore, this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				

**WP 29**  
**BILL OF QUANTITIES**  
**Robinson Trace Louis D'oir Drainage and Concrete Platform**  
**Summary**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CONCRETE WORKS</b>	
3.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 30**  
**BILL OF QUANTITIES**  
**Starwood Trace Speyside**

Item	Description	Quantity	Unit	Rate	Total
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway 470' x 20'				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. Note that failure to put effective safety measures in place will result in a "stop work order".		sum		
	Total carried to summary				
<b>2.0</b>	<b>CONCRETE WORKS</b>				
2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller				

	compactor for excavation works); remove vegetation; align roadway etc.				
a)	Excavate and cart away top layer 470' x 20' x 150mm in dept	<del>696</del> 175	yds <sup>3</sup>		
b)	Allow for alignment of roadway as identified/directed		sum		
	Collection				
2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling 9,400 ft <sup>2</sup>				
a)	Construct concrete roadway 470' x 20' x 6".	<del>696</del> 175	yds <sup>3</sup>		
b)	Slipper drain curb wall 470' x 6" x 8"	6	yds <sup>3</sup>		
c)	Slipper 4" thick x 12" wide	5	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	1	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
f)	Construct two (2) catch-pits 2'x2'x2' (internal dimensions) as directed. Cater for 4" concrete base	2	nr		
	Collection				
	Total carried to summary				
<b>3.0</b>	<b>DEMOBILIZE</b>				
3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				
a)	Allow for the removal of tools, equipment and unused materials offsite. Also include the removal of debris to an approved dump site		sum		

	Total carried to summary				
	<b>General Note</b>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore, this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				



**WP 30**  
**BILL OF QUANTITIES**  
**Starwood Trace Speyside**  
**Summary**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CONCRETE WORKS</b>	
4.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 32**  
**BILL OF QUANTITIES**  
**Top Hill Circular Road Belmont Farm Phase I**

<b>Item</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Total</b>
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway 636ft x 20ft				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. Note that failure to put effective safety measures in place will result in a "stop work order".		sum		
	Total carried to summary				
<b>2.0</b>	<b>CHIP SEAL WORKS</b>				
2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller				

	compactor ); remove vegetation; align roadway etc.				
a)	Excavate and cart away top layer 1,350' x 20' x 12 inches in depth	1,000	yds <sup>3</sup>		
b)	Allow for proper alignment of roadway		sum		
c)	Allow for Sub-base construction 300mm with imported backfill material (rotten rock) compacted in 3" layer to 97% MPD	1,000	yds <sup>3</sup>		
	Collection				
2.2	All inclusive of Crush Run, spread and compacted with 5 to 10 tonne roller in layers of 3" to finish at 6" thick; 2mm aggregate; application of bitumen to crush run and 2mm aggregate.				
a)	Road base construction using crushed run, supply, spread and compact in 3" layer to 98% MPD and apply bitumen to crush run	27,000	ft <sup>2</sup>		
b)	Supply and spread 2mm aggregate and apply bitumen to seal coat roadway	27,000	ft <sup>2</sup>		
	Collection				
	Total carried to summary				
<b>2.0</b>					
<b>3.0</b>	<b>CONCRETE WORKS</b>				
2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 1/2" HT steel, block work and backfilling material				
a)	Construct slipper drain curb wall 1,350' x 6" x 8"	18	yds <sup>3</sup>		

b)	Slipper 4" thick x 12" wide	15	yds <sup>3</sup>		
c)	Render outer face and top of curb wall	3	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
f)	Allow for the placing of 4" PVC sleeves with end caps every 300 feet under roadway (perpendicular to roadway)	64	ft		
	Collection				
	Total carried to summary				
<del>3.0</del>					
4.0	<b>DEMOBILIZE</b>				
3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				
a)	Allow for the removal of tools, equipment and unused materials offsite. Also include the removal of debris to an approved dump site		sum		
	Total carried to summary				
	<b>General Note</b>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore, this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				

**WP 32**  
**BILL OF QUANTITIES**  
**Top Hill Circular Road Belmont Farm Phase I**  
**Summary**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CHIP SEAL WORKS</b>	
<del>2.0</del> 3.0	<b>CONCRETE WORKS</b>	
<del>3.0</del> 4.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 33**  
**BILL OF QUANTITIES**  
**Top Hill Circular Road Belmont Farm Phase II**

<b>Item</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Total</b>
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway 636ft x 20ft				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. Note that failure to put effective safety measures in place will result in a "stop work order".		sum		
	Total carried to summary				
<b>2.0</b>	<b>CONCRETE WORKS</b>				
2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller				

	compactor for excavation works); remove vegetation; align roadway etc.				
a)	<del>Allow for the removal of loose material and compact roadway with 10 tonne roller to 97% MPD</del> Excavate and cart away top layer 150mm in depth	258	sum yds <sup>3</sup>		
b)	<del>Allow for alignment of roadway as identified/directed</del>		sum		
	Collection				
2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling 13,960 ft <sup>2</sup>				
a)	Construct concrete roadway 698' x 20' x 6".	258	yds <sup>3</sup>		
b)	Slipper drain curb wall 698' x 6" x 8"	9	yds <sup>3</sup>		
c)	Slipper 4" thick x 12" wide	8	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	1.3	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
f)	Allow for the placing of 4" PVC sleeves with end caps every 300 feet under R/C roadway (perpendicular to roadway)	70	ft		
	Collection				
	Total carried to summary				
3.0	<b>DEMOBILIZE</b>				
3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				

a)	Allow for the removal of tools, equipment and unused materials offsite. Also include the removal of debris to an approved dump site		sum		
	Total carried to summary				
	<b>General Note</b>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore, this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				



**WP 33**  
**BILL OF QUANTITIES**  
**Top Hill Circular Road Belmont Farm Phase II**  
**Summary**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CONCRETE WORKS</b>	
3.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 34**  
**BILL OF QUANTITIES**  
**Top Hill Circular Road Belmont Farm Phase III**

<b>Item</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Total</b>
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. Note that failure to put effective safety measures in place will result in a "stop work order".		sum		
	Total carried to summary				
<b>2.0</b>	<b>CONCRETE WORKS</b>				

2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation; align roadway etc.				
a)	<del>Allow for the removal of loose material and compact roadway with 10 tonne roller to 97% MPD</del> Excavate and cart away top layer 150mm in depth	296	sum yds <sup>3</sup>		
b)	<del>Allow for alignment of roadway as identified/ directed</del>		sum		
	Collection				
2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling 16,000 ft <sup>2</sup>				
a)	Construct concrete roadway 800' x 20' x 6".	296	yds <sup>3</sup>		
b)	Slipper drain curb wall 800' x 6" x 8"	10	yds <sup>3</sup>		
c)	Slipper 4" thick x 12" wide	9	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	1.5	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
f)	Allow for the placing of 4" PVC sleeves with end caps every 300 feet under R/C roadway (perpendicular to roadway)	80	ft		
	Collection				
	Total carried to summary				
3.0	<b>DEMOBILIZE</b>				
3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				

a)	Allow for the removal of tools, equipment and unused materials offsite. Also include the removal of debris to an approved dump site		sum		
	Total carried to summary				
	<b>General Note</b>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore, this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				

**WP 34**  
**BILL OF QUANTITIES**  
**Top Hill Circular Road Belmont Farm Phase III**  
**Summary**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CONCRETE WORKS</b>	
3.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 35**  
**BILL OF QUANTITIES**  
**Top Hill Road (RIGHT) Belmont Farm Phase I**

<b>Item</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Total</b>
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway 609ft x 20ft				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. Note that failure to put effective safety measures in place will result in a "stop work order".		sum		
	Total carried to summary				

<b>2.0</b>	<b>CONCRETE WORKS</b>				
2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation; align roadway etc.				
a)	<del>Allow for the removal of loose material and compact roadway with 10 tonne roller to 97% MPD</del> Excavate and cart away top layer 150mm in depth	226	sum yds <sup>3</sup>		
b)	<del>Allow for alignment of roadway as identified/ directed</del>		sum		
	Collection				
	<b>CONCRETE WORKS</b>				
2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling 12,180 ft <sup>2</sup>				
a)	Construct concrete roadway 609' x 20' x 6".	226	yds <sup>3</sup>		
b)	Slipper drain curb wall 609' x 6" x 8"	8	yds <sup>3</sup>		
c)	Slipper 4" thick x 12" wide	7	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	1	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
f)	Allow for the placing of 4" PVC sleeves with end caps every 300 feet under R/C roadway (perpendicular to roadway)	61	ft		
	Collection				
2.3	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 1/2 corrugated steel 8" c/c in both direction				

a)	Construct reinforce concrete box drain with catch pit. Box drain to be 200' x 2' wide x 2' depth (internal dimension). All wall to be 150mm thick.	200	ft		
	Collection				
	Total carried to summary				
<b>3.0</b>	<b>DEMOBILIZE</b>				
3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				
a)	Allow for the removal of tools, equipment and unused materials offsite. Also include the removal of debris to an approved dump site		sum		
	Total carried to summary				
	<b>General Note</b>				
1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore, this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				



**WP 35**  
**BILL OF QUANTITIES**  
**Top Hill Road (RIGHT) Belmont Farm Phase I**  
**Summary**

<b>Item</b>	<b>Description</b>	<b>Total</b>
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CONCRETE WORKS</b>	
3.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**WP 36**  
**BILL OF QUANTITIES**  
**Top Hill Road (RIGHT) Belmont Farm Phase II**

<b>Item</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Total</b>
<b>1.0</b>	<b>PRELIMINARIES</b>				
1.1	To cover the cost of Temporary Facilities; Signage, Survey works; Spray paint; Stakes; Caution tape; Insurance; Security; OSHA and EMA Requirements on roadway				
a)	Allow for temporary facilities, inclusive of miscellaneous Supplies: Spray paint, Stakes, Caution tape etc.		sum		
b)	Allow for insurance and Security		sum		
c)	Allow for PPE and other safety items for site workers, DFPFF staffs and the General Public in accordance with necessary regulations set by OSHA. In addition, consideration is to be given to Government's Covid-19 regulations. Note that failure to put effective safety measures in place will result in a "stop work order".		sum		
	Total carried to summary				

<b>2.0</b>	<b>CONCRETE WORKS</b>				
2.1	All inclusive of good working equipment (excavator, dump truck, 10 tonne roller compactor for excavation works); remove vegetation; align roadway etc.				
a)	<del>Allow for the removal of loose material and compact roadway with 10 tonne roller to 97% MPD</del> Excavate and cart away top layer 150mm in depth	206	sum yds <sup>3</sup>		
b)	<del>Allow for alignment of roadway as identified/ directed</del>		sum		
	Collection				
2.2	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling 11,120 ft <sup>2</sup>				
a)	Construct concrete roadway 556' x 20' x 6"	206	yds <sup>3</sup>		
b)	Slipper drain curb wall 556' x 6" x 8"	7	yds <sup>3</sup>		
c)	Slipper 4" thick x 12" wide	6	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	1	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
f)	Allow for the placing of 4" PVC sleeves with end caps every 300 feet under R/C roadway (perpendicular to roadway)	56	ft		
	Collection				
2.3	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 6x6x5 gauge BRC, block work, weep holes and backfilling for roadway 1,200 ft <sup>2</sup>				

a)	Construct concrete roadway 100' x 12' x 6"	22	yds <sup>3</sup>		
b)	Construct curb wall 100' x 6" x 8"	2	yds <sup>3</sup>		
c)	Construct 4" thick x12" wide slipper	1	yds <sup>3</sup>		
d)	Render outer face and top of curb wall	0.2	yds <sup>3</sup>		
e)	Allow for backfilling (rotten rock) behind 8" curb wall and general landscaping along roadway		sum		
	Collection				
2.4	All inclusive of formwork, cement/ sand render, concrete – 3000 psi, reinforcement – 1/2 corrugated steel 8" c/c in both direction				
a)	Construct reinforce concrete slab covered box drain. Box drain with 4" thick base - 12' long x 3' wide x 2' depth (internal dimension) – reinforcement 1/2" corrugated steel at 8" c/c. Slab cover to be 12 ft long x 4 ft 4 inches wide x 6 inches depth single layer 5/8" mat (both directions). All wall to be 150mm thick.		sum		
	Collection				
	Total carried to summary				
<b>3.0</b>	<b>DEMOBILIZE</b>				
3.1	All inclusive, removal of tools, equipment and unused materials off site. Also dispose of debris to an approved dump site				
a)	Allow for the removal of tools, equipment and unused materials offsite. Also include the removal of debris to an approved dump site		sum		
	Total carried to summary				
	<i>General Note</i>				

1	Prior to mobilizing, selected contractors must submit their onsite supervisor's name and contact number to the Project Manager in the Project Implementation Unit. Furthermore, this individual (supervisor) will be required to be onsite during project activities or at the Division's request. Note that failure in this regard will result in a "stop work order".				
2	A sufficiently detailed <b>Gantt Chart</b> and <b>Method Statement</b> are to be provided to the Project Implementation Unit for review prior to the commencement of works.				

**WP 36**  
**BILL OF QUANTITIES**  
**Top Hill Road (RIGHT) Belmont Farm Phase II**  
**Summary**

Item	Description	Total
1.0	<b>PRELIMINARIES</b>	
2.0	<b>CONCRETE WORKS</b>	
3.0	<b>DEMOBILIZATION</b>	
	Sub Total	
	VAT	
	Total	

**SCHEDULE III (a)**

Statutory Declaration (Private Company)

**REPUBLIC OF TRINIDAD AND TOBAGO**

**IN THE MATTER OF THE STATUTORY DECLARATIONS ACT CHAPTER 7:04**

I, \_\_\_\_\_, Director and  
(Name of director)  
authorized representative of \_\_\_\_\_  
(Name of company)

\_\_\_\_\_ a company duly incorporated and continued under the Companies Act 1995, with its registered  
office situate at \_\_\_\_\_  
(Address of company)

\_\_\_\_\_ the Island of Tobago/Trinidad in the Republic of Trinidad and Tobago, make oath and say as follows:-

1. I am the authorized representative of \_\_\_\_\_  
(Name of Company)  
\_\_\_\_\_ and duly authorized to give this declaration on its behalf.
2. The facts hereto deposed are true and correct and within my personal knowledge and belief save where otherwise stated to be based on information, in which case I verily believe same to be true and the source reliable.
3. I hereby certify that any signed contracts/letters of award of purchase orders that has been submitted by the Bidder in response to the Division's Access Road Programme 2018 is a true representation of works the Bidder has undertaken for this company

and that the Bidder was not terminated for any reason related to and or ancillary to material non – performance.

4. I have had my Attorney-at-Law explained to me and I fully understand the consequences, ramifications and implications of the aforesaid declaration.
5. I have deposed this declaration of my own free will, voluntarily and as a free and independent person without any threats, intimidation, promises and or inducement from anyone and after receiving legal advice and I hereby declare that I am mentally sound and in full control of my mental capacity, mind and body.
6. I, make this declaration conscientiously believing the same to be true and according to the Statutory Declarations Act, and I am aware that if there is any statement in this declaration which is false in fact, which I know or believe to be false or do not believe to be true, I am liable to fine and imprisonment

Declared at )  
this day )  
of 2021 )

Before me,

COMMISSIONER OF AFFIDAVITS

**SCHEDULE III (b)**

**Statutory Declaration (Private Individual)**

**REPUBLIC OF TRINIDAD AND TOBAGO**

**IN THE MATTER OF THE STATUTORY DECLARATIONS ACT CHAPTER 7:04**

I, \_\_\_\_\_  
(Name of person)  
\_\_\_\_\_ of  
(Occupation of person)  
\_\_\_\_\_  
(Address of person)  
\_\_\_\_\_  
\_\_\_\_\_

the Island of Tobago/Trinidad in the Republic of Trinidad and Tobago, make oath and say as follows:-

1. The facts hereto deposed are true and correct and within my personal knowledge and belief save where otherwise stated to be based on information, in which case I verily believe same to be true and the source reliable.
2. I hereby certify that any signed contracts/letters of award of purchase orders that has been submitted by the Bidder in response to the Division's Access Road Programme 2018 is a true representation of works the Bidder has undertaken for me personally and further that the Bidder was not terminated for any reason related to and or ancillary to material non – performance.
3. I have had my Attorney-at-Law explained to me and I fully understand the consequences, ramifications and implications of the aforesaid declaration.



4. I have deposed this declaration of my own free will, voluntarily and as a free and independent person without any threats, intimidation, promises and or inducement from anyone and after receiving legal advice and I hereby declare that I am mentally sound and in full control of my mental capacity, mind and body.
5. I, make this declaration conscientiously believing the same to be true and according to the Statutory Declarations Act, and I am aware that if there is any statement in this declaration which is false in fact, which I know or believe to be false or do not believe to be true, I am liable to fine and imprisonment

Declared at )  
this day )  
of 2021 )

Before me,

COMMISSIONER OF AFFIDAVITS