

<b>DATE SUBMITTED</b>	<b>QUERY #</b>	<b>TENDER NO.: DIQUD-2022-ITT-007 TENDER NAME: (BTB-012) Gabion Basket and Box Drain &amp; Retaining Wall, FRIENDSFIELD, CALDER HALL, TOBAGO</b>	<b>RESPONSE</b>	<b>DATE RESPONDED</b>
13.07.2022	1	How wide is the box drain	Width of existing drain to be used	8.2.22
13.07.2022	2	Are we doing both side of the Gabion Basket	No. Just the existing side to be continued and completed	8.2.22
13.07.2022	3	What is the height of the Gabion Basket	Height is to be staggered throughout to accommodate the height of the existing embankment	8.2.22
13.07.2022	4	What is the length of the box drain	The length of the box drain is 110m	8.2.22
13.07.2022	5	What is the length of the Gabion Basket Wall	The Gabion Basket Wall is 150m in length	8.2.22
13.07.2022	6	Would the Gabion Basket Wall be longer than 150m	No. The gabion Basket Wall is to continue from the existing wall and only run for 150m	8.2.22
13.07.2022	7	Would an addendum be issued for the drain at the front	No. Please include it in the overall cost	8.2.22
13.07.2022	8	Will roadway be paved using concrete	Roadway will be paved using concrete	8.2.22
20.07.22	9	There is inconsistent information for gabion basket that need to be clarified	Kindly be advised that new activities were added to the project BOQ, the revised scope of works has been issued and further, new submission deadline dates have also been included.	8.2.22
19.07.22	10	There are drawing omissions and other outstanding documents for the tender.	Kindly be advised that new activities were added to the project BOQ, the revised scope of works has been issued and further, new submission deadline dates have also been included.	8.2.22